
## EQUIPMENT TEST LIST COIN STATION TEST LINE

| CONTENTS |          |      |    |     |   |   |  |   | PAGE |   |   |   |
|----------|----------|------|----|-----|---|---|--|---|------|---|---|---|
| 1.       | GENERAL  |      |    |     |   |   |  | • |      |   |   | 1 |
| 9.1      | TST LN S | D-10 | 29 | 7-0 | 1 | • |  | • | •    | • | • | 2 |
|          |          |      |    |     |   |   |  |   |      |   |   |   |

## 1. GENERAL

- 1.01 This section provides an index and information access system to locate the standard tests applicable to equipment listed in the preceding table of contents. Test classification and frequency of periodic routine are also provided.
- 1.02 This Equipment Test List (ETL) is reissued to incorporate changes which are indicated by an arrow to the left of each line which has been changed.

- 1.03 Comments on this section should be made by following the instructions in Bell System Practices (BSP), Section 000-010-015.
- 1.04 Routine test informationis arranged in the following order from left to right: Section number, issue/addendum, test letter or paragraph number, test title, test class, frequency, and the last space is for a locally assigned job number.
- 1.05 Section 010-300-011 provides Equipment Test



## NOTICE

Not for use or disclosure outside the Bell System except under written agreement

## 9.0 CN STA TST LN

| • | FOR ALL UNITS |       |   |  |       |   |
|---|---------------|-------|---|--|-------|---|
| • | 201-833-501   | (7/0) | A | COIN PRESENT & GROUND REMOVAL TEST                                     | MW 6M |   |
| • |               |       | В | DIGIT RECEPTION TEST   | MW 12 | м |
| • |               |       | С | GROUND CHECK LOOP RESISTANCE & LEAKAGE TEST AND ADJUSTMENT (OPTION ZP) | MW 6M |   |
| • |               |       | D | COIN RETURN & COLLECT TEST   | MW 12 | м |
| • |               |       | F | COIN RELAY TIME TEST AND ADJUSTMENT                                    | MW 6M |   |
| • |               |       | G | MESSAGE REGISTER TEST (OPTIONS ZE, ZN, ZV)                             | MW 12 | м |
| • |               |       | Н | "TOUCH-TONE" DIALING TEST (OPTION X)                                   | MW 12 | M |
| • |               |       | I | FOREIGN EMF TEST (OPTION ZK)   | MW 6M |   |
| • |               |       | J | GROUND CHECK, LOOP RES. & LEAK TEST (OPT.ZO)                           | MW 3M |   |
| • | TROUBLE TESTS |       |   |  |       |   |
| • | 201-833-501   | (7/0) | E | 4-VOLT PWR SUPPLY TST & ADJ  | TT    |   |
| • |               |       | K | GRD CK, LOOP RES & LEAK ADJ (OPT.ZO)                                   | TT    |   |
| • |               |       | L | ACCESS & DISCONNECT TEST   | TT    |   |