# NO. 1 TRUNK CONCENTRATOR CIRCUIT SD-97569-01

# **TESTS**

# **COMMON SYSTEMS**

1. G	ENERAL		1.05 Lettered Steps: A letter a, b, c, etc, added to a step number in Part 3 or 4 of	
1.01	This section describes a method of testing the No. 1 trunk concentrator circuit.	g	this section, indicates an action which may or may not be required, depending on local conditions. The condition under which a lettered step or a	
1.02	This issue affects the Equipment Test List.	•	series of lettered steps should be made is given in the ACTION column, and all steps governed by	
1.03	The tests covered are:	E	the same condition are designated by the same letter within a test. Where a condition does not	
A.	Operational Test: This test checks the operation of the horizontal and		apply all steps designated by that letter should be omitted.	
	tical selection circuits. It also checks a alternate horizontal and vertical		2. APPARATUS	
pre	ference chains	2	Tests A and B	
В.	Trouble Time-Out: This test checks the operation of timers TO and		<b>2.01</b> 258C (dummy) plug.	
TM	[1	4	Tests A Through C	
C.	<b>Double Connection:</b> This test checks that a double connection		2.02 376A (make-busy) plugs as required.	
	rough the switch will operate the DCK ay and that the DCK lamp will light.		Tests A Through D	
		9	2.03 Blocking tools as required.	
D.	False Ground on TO Lead: This test checks that a false ground on		Test B	
	e TO lead will operate the XTO relay	10	2.04 Insulating tools as required.	
æ11	a was array womb was about		Test D	
1.04	It is recommended that the tests covered this section be performed during periods		2.05 Testing cord, 893 cord, 6 feet long, equipped with two 360A tools (1W13B cord), and two	
light	traffic.		KS-6278 connecting clips.	

## NOTICE

Not for use or disclosure outside the Bell System except under written agreement

#### 3. PREPARATION

STEP

#### **ACTION**

## **VERIFICATION**

#### **All Tests**

1a If ANI trunks are associated with switch under test—
At jack, key, and lamp panel on incoming trunk frame—
Operate MB\_ key for each ANI trunk associated with switch.

MB\_ lamp lighted for each trunk made busy.

If incoming trunks associated with switch under test are other than ANI trunks—
 At distant office—
 Arrange to have incoming trunks associated with switch under test made busy.

3 At trunk concentrator miscellaneous and alarm circuit—

Block MJC and MNC relays non-operated.

#### Tests A and B

At jack, key, and lamp panel associated with switch under test—
Operate MB\_ key for switch under test.

## 4. METHOD

STEP

## **ACTION**

## **VERIFICATION**

## A. Operational Test

- 5 Refer to Table A and select a switch, level, and vertical.
- 6 At jack, key and lamp panel associated with switch under test—
  Operate the LEVEL SELECT switch to the level selected in Step 5.
- 7 Operate MB\_ key associated with OGT located on the switch level selected in Step 5.

**Note:** Refer to office records for a listing of the outgoing trunks assigned to each level of each half switch.

8 At jack, key and lamp panel associated with switch under test— Insert 258C dummy plugs into the RCV and TRMT jacks associated with the outgoing OGT MB\_ lamp lighted (after released from service).

`



**STEP** 

**ACTION** 

**VERIFICATION** 

**TABLE A** 

SWITCH LEVEL	A HALF SWITCH VERTICAL	B HALF SWITCH VERTICAL
0	0	10
1	1	11
2	2	12
3	3	13
4	4	14
5	5	15
6	6	16
7	7	17
8	8	18
9	9	19
10	9	19
11	9	19

trunk appearing on the switch level selected in Step 5.

- 9 At jack, key, and lamp panel associated with switch under test-Insert 376A make-busy plug into TST jack associated with vertical selected in Step 5.
- 10 Momentarily operate ST key.
- 11 Momentarily operate RLS key.
- 12 At trunk concentrator frame-
- Manually operate TBL relay.
- 13 Repeat Steps 10 and 11.
- 14

Momentarily operate SWITCH RESTART key for switch under test.

15 Momentarily operate AR key.

16 Repeat Steps 5 through 15 for all switch levels and verticals in switch half "A" as shown in Table A.

ST, CT, and OGT ON\_ lamps lighted.

ST, CT, and OGT ON\_ lamps extinguished.

At jack, key, and lamp panel-AR lamp lighted.

MNR\_ lamp lighted for switch under test.

At trunk concentrator frame-TBL relay released.

At jack, key, and lamp panel-MNR\_ lamp extinguished.

AR lamp extinguished.

## SECTION 201-850-501

STEP	ACTION	VERIFICATION
17	Repeat Steps 1a through 15 for all switch levels and verticals in switch half "B" as shown in Table A.	
18	At jack, key and lamp panel associated with switch under test— Remove 376A make-busy plug from TST jack.	
19	Remove 258C dummy plugs from RCV and TRMT jacks.	
20	Restore $MB_{-}$ key associated with OGT made busy.	OGT MB_ lamp extinguished.
21c	If no further tests are to be made on this switch— Restore all incoming trunks to service.	If ANI incoming trunks— MB_ lamps extinguished.
22c	Restore MB_ key for switch under test.	Switch MB_ lamp extinguished.
23c	At trunk concentrator miscellaneous and alarm circuit— Remove blocking tools from MJC and MNC relays.	
B. Trou	ble Time-Out	
TO Timer	—Lower Half	
5	At jack, key and lamp panel associated with switch under test— Insert 376A make-busy plug into TST 0 jack associated with switch under test.	
6	Operate the LEVEL SELECT switch to level 0.	
7	Operate MB key associated with OGT located on level 0 of switch half "A".	OGT MB_ lamp lighted.
	<b>Note:</b> Refer to office records for a listing of the outgoing trunks assigned to each switch half.	
8	At trunk concentrator frame— Insulate contact 4M of relay OT0.	
9	At jack, key and lamp panel associated with switch under test— Momentarily operate ST key.	MJR_ lamp flashes then lighted for switch under test.  MNR_ lamp lighted for switch under test.  AR and ST lamps lighted.  OGT MB_ lamp extinguished.

STEP	ACTION	VERIFICATION		
10	Momentarily operate AR key.	AR lamp extinguished.		
11	Momentarily operate RLS key.	OGT MB_ lamp lighted. ST lamp extinguished.		
12	Remove the make-busy plug from TST 0 jack.			
13	Restore OGT MB key.	OGT MB_ lamp extinguished.		
14	Momentarily operate the SWITCH RESTART key.	MNR_ and MJR_ lamps extinguished.		
15	At trunk concentrator frame— Remove insulator from contact 4M of relay OT0.			
16	At jack, key and lamp panel associated with switch under test— Insert 376A make-busy plug into TST 5 jack of switch under test.			
17	Operate the LEVEL SELECT rotary switch to level 1.			
18	Operate MB_ key associated with OGT located on level 1 of switch half "A."	OGT MB_ lamp lighted.		
	<b>Note:</b> Refer to office records for a listing of the outgoing trunk assigned to each switch half.			
19	At trunk concentrator frame— Insulate contact 2B of relay OT0.			
20	Insert 258C dummy plug into REC and TRMT jacks of OGT.			
21	At jack, key and lamp panel associated with switch under test— Momentarily operate ST key.	MNR_ lamp flashes then lighted for switch under test. AR lamp lighted. ST lamp momentarily lighted.		
22	Momentarily operate AR key.	AR lamp extinguished.		
23	Momentarily operate ST key.	ST, CT, and OGT ON_ lamps lighted.		
24	Momentarily operate RLS key.	ST, CT, and OGT ON_ lamps extinguished.		
25	Repeat Steps 21 and 22 several times.	MJR_ lamp not lighted for switch under test.		

STEP	ACTION	VERIFICATION	
26	At trunk concentrator frame— Remove insulator from contact 2B of relay OT0.		
27	At jack, key and lamp panel associated with switch under test— Momentarily operate SWITCH RESTART key for switch under test.	MNR_ lamp extinguished.	
TM1 Time	er—Lower Half		
28	At trunk concentrator frame— Insulate contact 1B of relay VP0		
	<b>Note:</b> Relays may pulse during this operation if VP0 relay is operated.		
29	Momentarily operate the ST key.	MJR_ lamp momentarily lighted for switch under test. ST, CT, and AR lamps lighted. After approximately 1/2 second— MNR_ and OGT ON_ lamps lighted.	
30	Momentarily operate AR key.	AR lamp extinguished.	
31	Momentarily operate RLS key.	ST, CT, and OGT ON_ lamps extinguished.	
32	Momentarily operate SWITCH RESTART key for switch under test.	MNR_ lamp extinguished.	
33	Insulate contact 5B of relay VP8.		
	<b>Note:</b> Relays may pulse during this operation if VP8 relay is operated.		
34	Momentarily operate ST key.	MJR_ lamp flashes then lighted for switch under test. ST, CT, and AR lamps lighted. MNR_ lamp lighted for switch under test.	
35	Momentarily operate AR key.	AR lamp extinguished.	
36	Momentarily operate RLS key.	ST and CT lamps extinguished.	
37	Momentarily operate SWITCH RESTART key.	MJR_ and MNR_ lamps extinguished.	
38	At trunk concentrator frame— Remove the insulator from contact 1B of relay VP0 and contact 5B of relay VP8.		
39	Block relay SGA operated.		

STEP	ACTION	VERIFICATION
40	At jack, key, and lamp panel associated with switch under test— Momentarily operate ST key.	ST and AR lamps lighted. After approximately 1/2 second— MNR_ and MJR_ lamps lighted for switch under test.
41	Momentarily operate AR key.	AR lamp extinguished.
42	Momentarily operate RLS key.	ST lamp extinguished.
43	Remove blocking tool from SGA relay.	
44	Momentarily operate SWITCH RESTART key for the switch under test.	MNR_ and MJR_ lamps extinguished.
TO Time	r—Upper Half	
45	Operate TRF-TO key.	TFR-TO lamp lighted.
46c	If TFR-TO lamp flashes at 60 ipm after performing Step 45— Momentarily operate ST key and then RLS key.	
47	At trunk concentrator frame—Block non-operated ATB and OT1 relays.	
48	At jack, key and lamp panel associated with switch under test— Momentarily operate ST key.	ST lamp lighted.  After approximately 1/2 second—  MJR_ lamp flashes then lighted for switch under test.  MNR_ lamp lighted for switch under test.  AR lamp lighted.  After approximately 2 seconds—  OGT TO_ lamp lighted.
49	Momentarily operate AR key.	AR lamp extinguished.
50	Momentarily operate RLS key.	ST lamp extinguished.
51	Momentarily operate SWITCH RESTART key.	OGT TO_ lamp extinguished. MNR_ and MJR_ lamps extinguished.
52	Restore TFR-TO key.	TFR-TO lamp extinguished.
53	Operate the TFR-TOA key.	TFR-TOA lamp flashes at 60 ipm.
54	Momentarily operate the ST key.	ST and TFR-TOA lamps lighted.
		After approximately 1/2 second—MJR_ lamp flashes then lighted for switch under test. MNR_ lamp lighted for switch under test.

STEP	ACTION	VERIFICATION	
		AR lamp lighted. After approximately 2 seconds— TOA lamp lighted for switch under test.	
55	Momentarily operate AR key.	AR lamp extinguished.	
56	Momentarily operate RLS key.	ST lamp extinguished	
57	Momentarily operate SWITCH RESTART key.	TOA lamp extinguished for switch under test. MNR_ and MJR_ lamps extinguished.	
58	Restore TFR-TOA key.	TFR-TOA lamp extinguished.	
59	Restore OGT MB_ key.	OGT MB_ lamp extinguished.	
60	Remove blocking tools from ATB and OT1 relays.		
61	At jack, key and lamp panel associated with switch under test— Remove the make-busy plug from TST 5 jack of the switch.		
62	Remove dummy plugs from RCV and TRMT jacks.		
TM1 Tim	er—Upper Half		
63	At trunk concentrator frame— Manually operate VPA relay and hold for at least 2 seconds.	At jack, key and lamp panel associated with switch under test— Within 2 seconds— TFR-TO or TFR-TOA and AR lamps lighted.	
64	Momentarily operate AR key.	AR lamp extinguished.	
65	Repeat previous step until TFR-TO and TFR-TOA lamps are lighted at least once each.		
	<b>Note:</b> Traffic must be coming in to both halves of the switch in order for both lamps to be lighted once each.		
66	Release VPA relay.		
67	At jack, key and lamp panel associated with switch under test— Momentarily operate RESTART key.	At jack, key and lamp panel associated with switch under test— TFR-TO or TFR-TOA lamps extinguished.	
68	At trunk concentrator frame— Manually operate VPB relay and hold for at least 2 seconds.	At jack, key and lamp panel associated with switch under test— Within 2 seconds— TFR-TO or TFR-TOA lamp lighted.	

STEP	ACTION	VERIFICATION
69	Release VPB relay.	
70	At jack, key, and lamp panel associated with switch under test—  Momentarily operate RESTART key.  At jack, key and lamp panel— TFR-TO or TFR-TOA lamp extinguish	
71	At trunk concentrator frame—Block OTL relay nonoperated and ATB1 relay operated.	
72	Manually operate VPA relay and hold for at least 2 seconds.  At jack, key, and lamp processing switch under test—  TFR-TO or TFR-TOA not	
73	Removing blocking tools from OTL and ATB1 relays.	
74d	If no further tests are to be made on this switch— Restore all incoming trunks to service.	If ANI incoming trunks—MB_ lamps extinguished.
75d	Restore MB_ key for switch under test.	Switch MB_ lamp extinguished.
76d	At trunk concentrator miscellaneous and alarm circuit— Remove blocking tools from MJC and MNC relays.	
C. Doub	ble Connection	
4	At jack, key and lamp panel associated with switch under test— Insert 376A make-busy plug into TST 4 jack of switch under test.	
5	Operate the LEVEL SELECT rotary switch to level 0.	
6	Operate MB_ key associated with OGT located on level 0 of switch half "A."	OGT MB_ lamp associated with level 0 lighted.
•	<b>Note:</b> Refer to office records for a listing of the outgoing trunks assigned to each switch half.	
7	Insert 258C dummy plug into REC jack of trunk made busy.	
8	Momentarily operate the ST key.	ST, CT, and OGT ON_ lamps lighted. OGT MB_ lamp associated with level 0 extinguished.

## **SECTION 201-850-501**

STEP	ACTION	VERIFICATION
9	At trunk concentrator frame—Block VP5 relay non-operated.	
10	At jack, key, and lamp panel associated with switch under test— Insert 376A make-busy plug into TST 5 jack of switch under test.	
11	At trunk concentrator frame— Manually operate switch hold magnet number 5.	
12	Remove blocking tool from VP5 relay.	
13	Manually operate VP4 and VP5 relays of switch under test.	DCK_ and AR lamps lighted.  MNR_ and MJR_ lamps lighted for switch under test.
14	At jack, key, and lamp panel associated with switch under test— Momentarily operate RLS key.	DCK_, OGT ON_, ST, and CT lamps extinguished. OGT MB_ lamp lighted.
15	Momentarily operate SWITCH RESTART key.	MNR_ and MJR_ lamps extinguished.
16	Momentarily operate AR key.	AR lamp extinguished.
17	Restore OGT MB_ key.	OGT MB_ lamp extinguished.
18	Remove the 376A plugs from TST 4 and TST 8 jacks and dummy plug from REC jack of OGT.	
19c	If no further tests are to be made on this switch— Restore all incoming trunks to service.	If ANI trunks— Incoming trunk MB_ lamps extinguished.
20c	At trunk concentrator miscellaneous and alarm circuit— Remove blocking tools from MJC and MNC relays.	

## D. False Ground on TO Lead

4 At the incoming trunk terminal strip on the trunk concentrator frame—Ground any TO lead for any incoming trunk.

At jack, key, and lamp ground associated with switch under test— AR and XTO\_ lamps associated with switch under test lighted.

5 Remove ground from TO lead.

STEP	ACTION	VERIFICATION
6	At jack, key, and lamp panel associated with switch under test— Momentarily operate AR key.	AR lamp extinguished.
7	Momentarily operate SWITCH RESTART key associated with switch under test.	XTO_ lamp extinguished.
8c	If no further tests are to be made on this switch— Restore all incoming trunks to service.	If ANI incoming trunks—MB_ lamps extinguished.
9с	At trunk concentrator miscellaneous and alarm circuit— Remove blocking tools from MJC and MNC relays.	
	6 7 8c	At jack, key, and lamp panel associated with switch under test— Momentarily operate AR key.  Momentarily operate SWITCH RESTART key associated with switch under test.  If no further tests are to be made on this switch— Restore all incoming trunks to service.  At trunk concentrator miscellaneous and alarm circuit— Remove blocking tools from MJC and MNC