BELL SYSTEM PRACTICES Station Operations Manual Major Station Systems SECTION C71.861.11 Issue 1, April, 1962 AT&TCo Standard

SWITCHING SYSTEM NO. 400

KEY TELEPHONE LINE AND ADD-ON CIRCUIT

OPERATION TESTS

1.00 GENERAL

1.01 This section covers the following tests:

A. Central Office Line Test, Using Key Telephone Unit Not Associated with Add-On Circuit: Checks that the key telephone equipment is selected by the key telephone set and holds properly.

B. Station Line Test, Using Key Telephone Unit Not Associated with Add-On Circuit: Checks that the key telephone equipment is selected by the key telephone set and holds properly.

C. Add-On Circuit Test, Outgoing Call by Station: Checks the following features: (a) seizure of attendant station line, (b) holding of station line, (c) seizure of central office line, and (d) transfer of station line to central office line.

D. Add-On Circuit Tests, Incoming Call to Station: Checks the following features: (a) seizure of attendant central office line, (b) holding of central office line, (c) seizure of station line, (d) transfer of central office line to station line, and (e) disconnect control by called station.

1.02 Tests C and D require action and verification at an attendant station (a key telephone set where a central office line, associated station line, hold key, and transfer key appear) and a nearby station.

1.04 Test D requires action and verifications at a location where an incoming central office call can be placed.

2.00 METHOD

STEP

.

ACTION

VERIFICATION

CO dial tone heard.

Busy tone heard.

Test line seized.

Handset goes dead.

CO line lamp lights steadily.

CO line lamp starts winking.

<u>A. Central Office Line Test, Using Key Telephone Unit Not</u> <u>Associated with Add-On Circuit</u>

 At key telephone set: Depress CO line pickup key.

2 Remove handset from switchhook.

If testing CO line in nonhunting group, dial number of CO line under test.
OR
If testing CO line in hunting group, dial CO test line.

- 4 Depress and release HOLD key.
- 5 Hang up handset.
- 6 Depress CO line pickup key.

1

STEP	ACTION	VERIFICATION
7	Remove handset from switchhook.	Busy tone or test line heard. CO line lamp lights steadily.
8	Hang up handset.	CO line lamp extinguished.
B. Station Line Test, Using Key Telephone Unit Not Associated with Add-On Circuit		
1	At key telephone set: Depress station line pickup key.	
2	Remove handset from switchhook.	Dial tone heard. Station lamp lights steadily.
3	Dial number of station line under test.	Busy tone heard.
4	Depress and release HOLD key.	Station lamp starts winking. Handset goes dead.
5	Hang up handset.	
6	Depress station line pickup key.	
7	Remove handset from switchhook.	Busy tone heard.
8	Hang up handset.	Station lamp extinguished.
C. Add-On Circuit Test, Outgoing Call by Station		
1	At nearby station:	At attendant station:
1	Place call to attendant station.	Audible signal heard.
		Station lamp flashes.
2	At attendant station:	At attendant station: Station lamp lights steadily.
	Depress station line pickup key, re- move handset from switchhook.	Audible signal silenced.
		Talking connection established.
3	At attendant station: Depress and release HOLD key.	Station lamp starts winking.
4	At attendant station: Depress associated CO line pickup key.	CO dial tone heard. CO line lamp lights steadily.
5	If CO line is in nonhunting group, dial number of CO line under test.	Busy tone heard.
	OR If CO line is in hunting group, dial CO test line.	Test line seized.
6	Depress TRANSFER key.	Trunk lamp remains lighted.
7	Release TRANSFER key.	Station lamp lights steadily. At attendant station and nearby station: Busy tone or test line heard.

0 0

 \bigcirc

O O

ISS 1, SECTION C71.861.11

STEP ACTION

8 At attendant station: Hang up handset.

9 At nearby station: Hang up handset.

VERIFICATION

CO line, station lamps remain lighted. At nearby station: Busy tone or test line heard.

At attendant station: , CO line, station line lamps extinguished.

When incoming call is received, au-

D. Add-On Circuit Test, Incoming Call to Station

1 At attendant station: Obtain incoming call over CO line.

- 2 Depress CO line pickup key, remove handset from switchhook.
- 3 Request CO call to remain connected.
- 4 Depress and release HOLD key.
- 5 Depress station line pickup key.
- 6 Dial number of nearby station.

7 At attendant station: When audible tone is heard, depress and release TRANSFER key, hang up handset.

8 At nearby station: Remove handset from switchhook.

9 At nearby station: Request central office call to disconnect after interval of 30 seconds, then hang up handset. CO line lamp starts winking.

CO line lamp lights steadily.

Talking connection established.

Dial tone heard. Station lamp lights steadily.

At nearby station: Audible signal heard.

dible signal heard. CO line lamp flashes.

At attendant station: Station line lamp flashes.

Talking connection established with CO line. At attendant station: Station line lamp lights steadily. CO line lamp lights steadily.

At attendant station: When nearby station hangs up, CO line, station lamps extinguished.

> Page 3 3 Pages